

Making Engineered Timber Flooring





Engineered Timber process

- 1. The tree is de barked
- 2. Quarter sawn into strips
- 3. Air stack fillet dried
- 4. Kiln dried
- 5. Top hardwood species cut into desired profile... 1,2 or 3 strip
- 6. The core cross hatched plies of timber on a base
- 7. Layers glued and pressed together
- 8. The top layer sanded, coated and UV cured





